

# Khutala Colliery

## Back-bye Management Strategy

5 June 2025



From Success to Significance  
From Success to Significance

# Agenda

1

Background

2

Historical Roof Support Strategies

3

Backbye Ground Conditions

4

Backbye Fog Incidents

5


Backbye Management Strategy



# Background




# Khutala Colliery Locality



Location: Western side of the Witbank Coal Field (WCF), northern part of South Africa's Karoo Basin.



# Generalized Stratigraphy For Khutala Colliery



## Brief Description on Economical Deposits

#5 seam roof composition: silty/sandy mudstone roof

- Avg thickness  $\approx 2.0\text{m}$  (approximate seam thickness range  $1.5\text{m} - 2.5\text{m}$ )
- Avg depth  $\approx 30\text{m}$  (approximate depth range  $20\text{m} - 50\text{m}$ )

#4 seam roof composition: laminated sandstone overlain by mudstone/sandy mudstone

- Avg thickness  $\approx 5.41\text{m}$  (approximate seam thickness range  $0.24\text{m} - 8.51\text{m}$ )
- Avg depth  $\approx 51.42\text{m}$  (approximate depth range  $60\text{m} - 80\text{m}$ )


#2 seam roof comp: mudstone/sandy mudstone

- Avg thickness  $\approx 5.71\text{m}$  (approximate seam thickness range  $0.18\text{m} - 10.26\text{m}$ )
- Avg depth  $\approx 75.28\text{m}$  (approximate depth range  $80\text{m} - 100\text{m}$ )




# Mined Areas And Remaining Underground Reserves

2 Seam Layout (Reserves and Mined Out)



4 Seam Layout (Reserves and Mined Out)



# Historical Roof Support Strategies



# Khutala Historical Systematic Support Strategies

2x 1.5m x 16mm mechanical bolts support



Voest onboard support (staggered bolts)



Support Type and Age

- **Year 1991**  
2 x 1.5m x 16mm mechanical bolts support installed

- **Year 1997**  
Voest onboard support (staggered bolts)

3 x 1.8m x 18mm point anchor resin



4 x 1.8m x 20mm full column resin bolts



- **Year 1998**  
3 x 1.8m x 18mm point anchor resin

- **Year 2004**  
4 x 1.8m x 20mm full column resin bolts



# Current Backbye Ground Conditions



# Backbye Conditions

## Description of conditions

Most areas has been previously supported with 2 × 1.5m × 16mm long mechanical anchor roof bolts at a row spacing +/-2m.

Delaminated loose roof slabs have been identified within these areas thus; highlighting the risk of further roof slabbing.

Roof slabbing occurs between and around the roof bolts, resulting in ineffective loose/un-tensioned hanging roof bolts.

## Images



# Backbye Conditions

## Description of conditions

Major geological structures (Faults and Dykes), not previously fully supported.

Roof debris accumulation in the roof nets, which requires bleeding.

Torn roof nets which require replacement

## Images



# Backbye Fog Incidents



# Back-bye Fog Incidents

## 2 Seam Spine Belt (Sp.107-108)

Immediate roof slabbing consisting of a weak laminated coal stratum with an estimated thickness of 0.3 m, dislodged from an inadequately supported area resulting in “skin” failure of rock under its weight.

The area had been previously supported with 2 x 1.5m long x 16mm diameter mechanical anchor roof bolts per row, rows spaced at  $\approx 3.0$  m, hence the failure occurred between the roof bolts.

## 4 Seam Service Road (Backbye areas)

Immediate roof slabbing consisting of a weak laminated coal stratum with an estimated thickness of 0.2m, dislodged from an inadequately supported area, resulting in “skin” failure of the coal layer under its weight.

The roadway has been previously supported with 2 x 1.5m long x 16mm diameter mechanical anchor roof bolts per row, rows spaced at  $\approx 2.0$  m

### Images



### Images



# Back-bye Fog Incidents

## 242 Belt Road

Roof slabbing of the laminated sandstone roof took place along 242 Belt Road between leg structures 85 and 86. A roof slab of approximately **1.5m (length) × 1.5m (width) × 0.03m (thickness)**, fell onto the belt structure. This resulted in a pull key wire being damaged by the failure.

The cause of the roof slabbing is due to the time dependent deterioration.

## 4E2 Belt (Sp.8-9)


Pillar sidewall scaling consisting of a coal block with an estimated thickness of **0.3m**, length of **2.0m**, and width of **1.0m**. No areal support (sidewall netting/welded mesh support) was installed at the time of failure

Heavy rainfalls also contributed to the added weight of the overlying strata (increasing vertical load) and thus causing the pillars to scale as a response to the additional load.

## Images



## Images



# Back-bye Fog Incidents


## 2E3 Traveling Road

Brow failure with estimated dimensions of **7.0m** wide x **1.3m** length x **1.7m** thick = **15.47m<sup>3</sup>** dislodged from within the main brow with a thickness of **≈3.1m** and fell into 2E3 traveling road

The mining dimensions, bord width and mining height were measured as **7.0 m** and **4.2m** (under the brow) – **7.3 m** (to the sandstone roof) respectively.

The above mining parameters are a consequence of total seam mining to accommodate the construction of air-crossings at the time.

## Images



# Backbye Management Strategy



# Back-bye Management Process Flow

- Geotechnical inspection done by the RE department, risk rank conditions and issue recommendations

Back-bye inspections by RE

- Back-bye hazard plan and a heat map are updated as per the conditions observed by RE and made available on the cloud for execution team to track

Hazard Plan and heat map

Update of the heat map


- Back-bye execution team updates the heat map after the scope of work is executed

Scope of work execution

- Back-bye execution team executes the scope of work issued by the RE department



# Back-bye Management Standard Operating Procedures









DOC NO: 727  
VERSION: 3.0  
ISSUED: 2023/09/01  
REVIEW DUE: 2026/08/31

KHUTALA COLLIERY UNDERGROUND BACKBYE STRATA MANAGEMENT

**KHUTALA COLLIERY UNDERGROUND BACKBYE STRATA MANAGEMENT**

**OLD\_KHU\_SOP\_727\_ROCK ENG**

AUTHORISATIONS	NAME	POSITION	SIGNATURE	DATE
AUTHOR	Carol Dzimba	Section Rock Engineer		15/11/2023
REVIEWED BY	Pieter Le Roux	Acting Section Manager Underground		14/11/23
REVIEWED BY	Tsundzuka Nhlapho	Technical Service Manager		22/11/23
REVIEWED BY	Thabo Ramara	Mine Manager Underground		11/12/23
APPROVED BY	Mhlonipheni Buthelezi	General Manager		04/12/2023








DOC NO: 334  
VERSION: 3.0  
ISSUED: 2023/12/07  
REVIEW DUE: 2026/12/06

KHUTALA COLLIERY OUTBYE SUPPORT MEASURING

**KHUTALA COLLIERY OUTBYE SUPPORT MEASURING**

**OLD\_KHU\_SOP\_334\_ROCK ENG**

AUTHORISATIONS	NAME	POSITION	SIGNATURE	DATE
AUTHOR	Carol Dzimba	Rock Engineering Manager		29/11/2023
REVIEWED BY	Tsundzuka Nhlapho	Technical Services Manager		29/11/2023
REVIEWED BY	Thabo Ramara	Mine Manager Underground		30/11/2023
APPROVED BY	Mhlonipheni Buthelezi	General Manager		30/11/2023








DOC NO: 052  
VERSION: 6.0  
ISSUED: 2024/06/21  
REVIEW DUE: 2027/06/20

BLEEDING OF NETS UNDERGROUND

**BLEEDING OF NETS UNDERGROUND**

**OLD\_KHU\_SOP\_052\_UG MINING**

AUTHORISATIONS	NAME	POSITION	SIGNATURE	DATE
AUTHOR	Xolani Sibiya	Acting Section Rock Engineer		6/18/2024
REVIEWED BY	Joshua Mashele	Section Manager Backbye		6/20/2024
REVIEWED BY	Sibusiso Sibiya	Mine Manager Underground		6/21/2024
APPROVED BY	Mhlonipheni Buthelezi	General Manager		6/25/2024






DOC NO: 707  
VERSION: 4.0  
ISSUED: 2023/05/01  
REVIEW DUE: 2026/04/30

KHUTALA COLLIERY- OUTBYE SPECIAL SUPPORT

**KHUTALA COLLIERY- OUTBYE SPECIAL SUPPORT**


**OLD\_KHU\_SOP\_707\_ROCK ENG**

AUTHORISATIONS	NAME	POSITION	SIGNATURE	DATE
AUTHOR	Carol Dzimba	Section Rock Engineer		4/20/2023
REVIEWED BY	Thabo Ramara	Mine Manager Underground		4/20/2023
APPROVED BY	Raymond Makgota	General Manager		4/20/2023




# Back-bye Support Rule


## Systematic roof and sidewall welded mesh support pattern



## Suspension of roof mesh with hydraulic/temporary support jacks



## Systemic roof welded mesh support pattern using double nuts/Q-links



# Back-bye Fog Incidents

Systemic roof and sidewall welded mesh support pattern




Systemic roof welded mesh support pattern using double nuts/Q-links




Suspension of roof welded mesh with hydraulic/ temporary support jacks



# Geotechnical Inspections

ROCK ENGINEERING DEPARTMENT KHUTALA COLLIERY FARM IS-34 COLOGNE. KENDAL. 2230 Republic of South Africa			
2E2 Tail End and 2E3 Drive Area Strata Report			
To	M Kgopodthate		
cc	J Mashele; R. Maila; S. Sibiya		
From	D. Matumba		
Date	13 December 2024		
<b>1. Introduction</b> The 2 East 2 tail end/ 2 East 3 Belt drive area was visited by Dakalo Matumba (Senior Strata Control Officer) along with Joshua Mashele (Section Manager), Derrick Shube (Shift Overseer) and Sibusiso Sibiya (Mine Manager) to determine the ground conditions and integrity of support installed along the belt road area between split 102 and 106. This report outlines the findings and recommendations thereof.			

Scopes of work are drafted following inspections done by rock engineering in conjunction with the back-bye mining team to address support issues that cannot be fully addressed by the mine standard support rule. These scopes of work give guidance and support designs suited for the inspected conditions.

		DOC NO: BOW_011_CCV_PC3 VERSION: 2 ISSUED: 2024/05/28 REVIEW DUE: 2026/05/29			
CRITICAL CONTROL VERIFICATION					
BOW_011_CCV_PC3_25047_UG FOG_OUTBYE SUPPORT					
Risk Name: UG_FOG_V1.0 Isometrix Ref No: 25047		Risk Owner: Carol, Dzimba Critical Control Nr: 25047			
CONTROL DETAIL Maintain outbye support based on hazard plan and/or designated places of work and bleeding of nets / mesh					
CONTROL OBJECTIVE Preventing FOG related incidents in Travelling, dyke, stone work and conveyor roads as well as designated outbye working areas of the production sections					
TASK DESCRIPTION Verify and attach proof as required by the steps of this Verification. The verifier must ensure that he/she does each verification in a different area within his/her area of responsibility and ensure that Own employees and Contractors are covered.					
DESIGN STANDARD Installation of support according to Mine Specific Outbye Support Rule / standard  Example Roof 1. Roof mesh size: 4.8m X1.7m, consisting of appetures of 75mm X 75mm. 2. Four M20 full column resin grouted bolts installed 1.5 m apart in rows between existing end anchored bolts 3. Mesh sheet overlap of 0.2m  Sidewall 1. Sidewall supported installed as per mine standard  Strict adherence to the SOW (Scope of Work) issued by Rock Engineering personnel					
OPERATING STANDARD	VERIFICATION APPROACH	YES	NO	N/A	TASK COMMENTS

Critical Control Verifications for back-bye support verifications are scheduled monthly and assigned to both execution and rock engineering personnel. They are designed to track overall back-bye conditions and support status (actions are raised on Isometrix where non-compliance is identified).



## From Success to Significance




22

22

22

22

## SPINE BELT AND TRAVELLING ROAD



### Backbye Hazard Plan

A hazard plan outlining the ground conditions along the belt and travelling areas.

The areas are ranked according to the conditions observed:

- No areal support installed
- Area support installed
- Bleeding of nets required
- High-risk area (no support installed/old support installed)




# Backbye Management Strategy

## Special Support Using Gophers and Scaffolding

This strategy is utilized by the inhouse mining teams to install roof support over the conveyor belt by making use of portable hand-held roof bolter machines (Gophers) and using scaffolding to enable working over the conveyor belt whilst it is operating.



# Visuals And Support Design Sketch Of District Substation 1



# Scope Of Work Execution

## Specialized Support at MC



# Thank You

