



Implats – Impala Rustenburg operations

THE ADOPTION JOURNEY FOR THE PERMANENT WORKFACE AREAL MESH TRIAL AT IMPALA RUSTENBURG

Buntu Tati, Rock Engineering Manager, Impala Rustenburg
Kate Ntombela, Head of Safety, Impala Rustenburg
28 March 2025



MINERALS COUNCIL
SOUTH AFRICA

CONTENTS

1. Introduction
2. Journey to Zero Harm – 8 Point Safety Plan
3. Incident statistics and FOG statistics
4. Adoption process – Criteria, drop tests, procedures
5. Case study – Success story (E&F shaft) – Photos & safety recognition
6. Way Forward

INTRODUCTION – IMPALA WESTERN LIMB OPERATIONS



- Locality: 145 km North-West of Johannesburg



- Shafts: Thirteen (13) operational shafts (including Bafokeng)



- Reefs mined: UG2 & Merensky



- Mining Methods: Conventional scattered breast & trackless mining




- Mining Depth: 30m – 1500m below surface



- Employees: +-49 000 (including Bafokeng)

We are here




- Annual ounce output: +-1 800 000 oz
- No of stoping crews: 816 crews




ZERO HARM - IMPLATS - 8 POINT SAFETY PLAN




JOURNEY OF INITIATIVES & IMPACT ON FOG INCIDENTS



IMPALA FALL OF GROUND ACCIDENT SUMMARY 2004 – 2024



IMPALA FALL OF GROUND FATAL SUMMARY 2004 – 2024



LESSONS LEARNT FROM OTHER ADOPTING MINES

Learnings from adopting mines

- Mesh **design** is critical;
- **Engagement** with all **stakeholders** at the **start**;
- During trials, if any **sub-standard installation, poorly suspended mesh** or inadequate linking of mesh **creates a false sense of security**;
- **Adopting mines** have realized a **reduction in FoG injuries** and **severity**;
- **Additional** support time and **cost** requirement **outweighed** by **safety benefit**;
- **Production** was **sustained** and **worker morale** improved.

Mponeng (Gold)



Sibanye Stillwater (PGM)




Bambanani (Gold)




Masimong (Gold)




MOSH ADOPTION PROCESS FOR PERMANENT MESH TRIAL



DESIGN REQUIREMENTS



- **Mesh dimensions conform to Impala support type and spacing**
- Mass to be supported: **2-ton mass** for stoping,
- **Drop Height: 100mm** above net.
- **Maximum deflection** after drop: **300mm** from original position of net.



DROP TEST CONDUCTED ON VARIOUS PRODUCTS

2 Ton Drop Test



Drop Height 100mm



Max Allowable Sag 300mm deflection



- Drop tests conducted on various products
- Various test configurations:
 - Prop to Prop
 - Prop to Bolt
 - Bolt to Bolt
- Supplier product development to meet design specifications

CRITERIA FOR THE TRIALS

- **Mesh** must be able to **contain key blocks** up to **2 tons**, with **acceptable deformation** (“survival zone”).
- **Support accessories** must be **compatible** with **current support system**.
- **Mesh** installation must **integrate** into the **current mining cycle** without **affecting crew productivity**.
- **Labour compliment** of the crew must be **suitable** for the **mesh installation**.
- **Logistical** and **storage** (surface and underground) requirements must be **adequate**.




2-ton drop test:
permanent mesh





DROP TESTS SIMULATIONS




INSTALLATION SEQUENCE



LEGEND:

-  Temporary support units
-  New tendon support units
-  Tendon support units
-  Blast-on mesh


Tendon drilled and installed as close as practically possible into the corner of the stope panel



SHIFT 1: DRILLING

1. To install the **first row of blast-on mesh** in the stope panel, it will be necessary to **install 2-rows of Camlok props** to clamp the blast-on mesh to the hanging wall, **1 row along the front** and **1 row along the back end** of the blast-on mesh.
2. It is important to note that the first row of permanent blast-on mesh will **also require two rows of tendon support units** to pin the mesh to the hanging wall.
3. **After the blast the next line of blast-on mesh will only require 1-row of Camlok props and 1-row of tendon support units** installed in the immediate face area.

INSTALLATION PROCEDURE OF BLAST-ON MESH IN STOPE PANELS



Joining the Blast-on Mesh with Connection Clips



Cutting Tool



Spike Plate



Seven connection clips are installed per running metre of the mesh

MESH COMPONENTS


Spike plate



Current Washer




Prototype – Spike Plate / Washer



Clip

Deformation of

Prototype – Spike Plate / Washer



- Mesh is supplied with spike plates and connecting clips
- Spike plates not suitable for current support tendon
- New prototype washers compatible with all mesh supplier were developed
- Tests conducted on various prototype options and currently available and in use for operations

FEEDBACK FROM JOINT TEAM VFL INSPECTION VISITS

- The vast majority **crews** are **positive** about the concept of permanent mesh;
- Some **panel advances** were found to be **less than 1.0m** per blast resulting in **large mesh overlaps** and wastage;
- **Crews reported** that size of mesh roll make **installation difficult** and **requires** as many as **4 people** to handle;
- **Smaller mesh sizes** are **easier to handle** and install
- The **quality of mesh installation** varied but seems to **improve with constant coaching and experience.**



No.16 shaft

Impala and Minerals council team inspection of 16 shaft mesh trial site



KEY NOTES - PROGRESS UPDATE

- **Adoption** commenced in **September 2023**;
- **Three suppliers** were **identified** through consultation with various stakeholder forums;
- **Initial drop tests unsuccessful, suppliers told to redesign** to match current safety net performance;
- **New tests** in February 2024 were **successful** and underground **trials** were **approved**;
- **Trials** currently underway **on all (10x) Impala Rustenburg** shafts (at least 1 trial site per shaft).
- **+17 000 mesh segments** installed to date **translates to 38 000 m² of hangingwall covered** by mesh
- **Trial extended** to the **(3x) Bafokeng** operations.

BLAST-ON MESH TRIALS LEARNINGS

- Mesh **roll dimensions** are critical, should **match** in-stope **bolt spacing** and blast advance to minimise wastage.
- **Logistics** and **storage** capacity envisaged as a challenge during full roll out.
- **Proper tensioning** required to **minimise damage** from blasting and/or scraping activities.
- Mesh “**mass**” versus “**strength**” versus “**cost**” trade offs.


Technical benefits:

- **Reduced area** to be examined and made safe.
- Back area **fully covered**.
- **No removal** of the temporary nets required.
- Rock mass failure (FoG) **risk is minimized**.

CREW 0554D - E&F SHAFT SUCCESS STORY

GEOTECHNICAL CONDITIONS AT E&F – GCD “G” :

- **Rockmass** characterized by **blocky** with **keyblock** features.
- The intersection of the **joints, fault, dykes** etc affects the stability of the hanging wall.
- **Lateral faulting** between the **triplets** and the top contact of UG2 reef. Triplets in **close proximity** to top **UG2 reef contact** (50cm to 100cm).
- **Near-surface weathering** (30 – 100 metres below surface).
- Surface **water dripping**.
- Many **blocks** were **abandoned** in the past due to the conditions.
- **Area re-assessed** to be mined **with Permanent mesh**.



QUALITY OF INSTALLATION

- ✓ Total coverage & flush against hangingwall
- ✓ Well tensioned
- ✓ Excellent joining of mesh segments
- ✓ Minimal mesh damage
- ✓ Neat with minimal loose strands




LARGE FALL CAUGHT BY PERMANENT MESH

- In September 2024, the **morning shift** crew **discovered a FoG at 2C45 P4EC within the face area after the blast.**
- The **FoG** is believed to have **occurred at the during the blast.**
- The **FoG** was **successfully contained by the permanent mesh** within the face area installed.
- The **FoG** was observed to **only occur between the last permanent mesh row and face** (newly exposed hangingwall face area).
- The **size of the rocks** was measured to be approximately **4.0m in length, 2.5m in width and 0.7m in fall out thickness.** The total mass of the FoG is **approximately 18 tonnes.**



CREW 0554D - E&F SHAFT SUCCESS STORY

- **Began installing** permanent mesh since **June 2024**.
- The crew's **production performance** before & during the trail was **sustained (flat trend)**.
- The crew has demonstrated an excellent adoption to the mesh and have an exceptional installation quality.
- A decision was taken by management team to recognize and reward the team with T-shirts, certificates & a braai.



WAY FORWARD

- **Complete trials** on all shafts **by June 2025**.
- **Finalise operating model**, inclusion in **COP**, **draft Standards & Procedures**.
- **Quantify impact** on **human effort** to **transport** and **install permanent mesh**.
- **Firm-up** on the **roll out strategy** – Current thinking: **Geotechnical Area** and **Risk-based** approach.
- It carries a **high intensity cost** – a risk based roll out strategy will be employed.
- The **replacement** of the **temporary safety nets** with **permanent mesh** will **partially offset** the **cost**.
- The **cost benefit** from the **lives saved** would **outweigh** the **expense** associated with **mesh implementation**.

PHOTOS OF MESH INSTALLATIONS

Trackless Bord & Pillar



Conventional Panels





THANK YOU